

CITY OF SPOKANE, WASHINGTON DEPARTMENT OF ENGINEERING SERVICES

KYLE TWOHIG, ENGINEERING OPERATIONS MANAGER

DAN BULLER, P.E., CITY ENGINEER

GARY KAESEMAYER, DIRECTOR OF STREETS

DAN KEGLEY, DIRECTOR OF WATER AND WASTEWATER

**** CONTRACT PROVISIONS ****

FOR:

RIVERSIDE DRIVE PHASE 2B

STPD-3850(006) - Federal Funding Source
funded in part by Washington State TIB (UAP)



February 23, 2018

ENGINEERING SERVICES FILE NO. 2015078

Riverside Drive Phase 2B

Engineering Services File No. 2015078

The Technical Material and data contained in these Contract Provisions were prepared under the supervision and direction of the undersigned, whose seal as a Professional Engineer licensed to practice as such in the State of Washington, is affixed below.



Approved [Signature] Date 2-20-18
(Engineering Operations Manager)

Approved [Signature] Date 2-21-18
(City Engineer)

Approved [Signature] Date 2-20-18
(Director -Streets)

Approved [Signature] Date 2/21/2018
(Director – Water and Wastewater)

TABLE OF CONTENTS

Item	Page
CALL FOR BIDS	ix
AMENDMENTS TO STANDARD SPECIFICATIONS.....	1
SPECIAL PROVISIONS	1-1
DESCRIPTION OF WORK	1-2
1-01 DEFINITIONS AND TERMS	1-2
1-01.3 Definitions.....	1-2
1-02 BID PROCEDURES AND CONDITIONS.....	1-4
1-02.1 Qualification of Bidder.....	1-5
1-02.2 Plans and Specifications.....	1-5
1-02.4 Examination of Plans, Specifications, and Site of Work	1-5
1-02.5 Proposal Forms.....	1-6
1-02.6 Preparation of Proposal.....	1-6
1-02.6(1) Recycled Materials Proposal.....	1-6
1-02.7 Bid Deposit	1-6
1-02.9 Delivery of Proposal, Option B.....	1-7
1-02.15 Pre-Award Information	1-9
1-03 AWARD AND EXECUTION OF CONTRACT	1-9
1-03.1 Consideration of Bids.....	1-9
1-03.1(1) Consideration of Bids	1-9
1-03.3 Execution of Contract.....	1-10
1-03.4 Contract Bond with Payment and Performance Bonds.....	1-11
1-04 SCOPE OF THE WORK	1-11
1-04.2 Coordination of Contract Documents, Plans, Special Provisions, Specifications, and Addenda	1-11
1-05 CONTROL OF WORK	1-12
1-05.4 Conformity With and Deviations From Plans and Stakes	1-12
1-05.7 Removal of Defective and Unauthorized Work.....	1-13
1-05.10 Guarantees	1-14
1-05.11 Final Inspections and Operational Testing.....	1-15
1-05.13 Superintendents, Labor and Equipment of Contractor	1-17
1-05.14 Cooperation With Other Contractors	1-17
1-05.15 Method of Serving Notices.....	1-18
1-05.16 Water and Power.....	1-18
1-06 CONTROL OF MATERIAL	1-18
1-06.6 Recycled Materials	1-20
1-07 LEGAL RELATIONS AND RESPONSIBILITIES TO THE PUBLIC	1-21
1-07.2 Sales Tax	1-21
1-07.5 Environmental Regulations.....	1-22
1-07.6 Permits and Licenses	1-23
1-07.9 Wages.....	1-24

1-07.9(3) Apprentices	1-24
1-07.11 Requirements For Nondiscrimination	1-27
1-07.13 Contractor's Responsibility for Work	1-28
1-07.15 Temporary Water Pollution/Erosion Control	1-28
1-07.16 Protection and Restoration of Property.....	1-29
1-07.17 Utilities and Similar Facilities.....	1-30
1-07.18 Public Liability and Property Damage Insurance	1-37
1-07.22 Use of Explosives	1-41
1-07.23 Public Convenience and Safety	1-41
1-07.24 Rights of Way.....	1-46
1-07.100 Survey Monument Perpetuation	1-47
1-08 PROSECUTION AND PROGRESS.....	1-50
1-08.0 Preliminary Matters	1-50
1-08.1 Subcontracting.....	1-52
1-08.4 Notice to Proceed and Prosecution of the Work.....	1-52
1-08.5 Time for Completion	1-54
1-08.9 Liquidated Damages.....	1-55
1-09 MEASUREMENT AND PAYMENT	1-56
1-09.1 Measurement of Quantities	1-56
1-09.7 Mobilization.....	1-56
1-09.9 Payments	1-56
1-09.13 Claims Resolution	1-57
1-10 TEMPORARY TRAFFIC CONTROL	1-58
1-10.2 Traffic Control Management	1-58
1-10.3 Traffic Control Labor, Procedures, and Devices	1-59
1-10.5 Payment.....	1-62
2-01 CLEARING, GRUBBING AND ROADSIDE CLEANUP	2-1
2-01.1 Description.....	2-1
2-01.3 Construction Requirements	2-1
2-01.4 Measurement.....	2-7
2-01.5 Payment	2-8
2-02 REMOVAL OF STRUCTURES AND OBSTRUCTIONS	2-9
2-02.1 Description	2-9
2-02.3 Construction Requirements.....	2-9
2-02.4 Measurement	2-14
2-02.5 Payment.....	2-14
2-03 ROADWAY EXCAVATION AND EMBANKMENT	2-16
2-03.1 Description	2-16
2-03.2 Materials.....	2-16
2-03.3 Construction Requirements.....	2-16
2-03.4 Measurement	2-22
2-03.5 Payment.....	2-23
2-06 SUBGRADE PREPARATION	2-25
2-06.1 Description	2-25
2-06.3 Construction Requirements.....	2-25
2-06.5 Measurement and Payment	2-26
2-07 WATERING	2-26

2-07.1 Description.....	2-26
2-07.3 Construction Requirements	2-27
2-07.5 Payment.....	2-27
2-09 STRUCTURE EXCAVATION	2-27
2-09.3 Construction Requirements.....	2-27
2-09.4 Measurement	2-29
2-09.5 Payment.....	2-29
2-12 CONSTRUCTION GEOSYNTHETIC	2-30
2-12.5 Payment	2-30
4-04 BALLAST AND CRUSHED SURFACING	4-1
4-04.3 Construction Requirements.....	4-1
4-04.4 Measurement	4-3
4-04.5 Payment.....	4-3
5-04 HOT MIX ASPHALT	5-1
5-04.2 Materials.....	5-1
5-04.3 Construction Requirements.....	5-1
5-04.4 Measurement	5-13
5-04.5 Payment.....	5-14
5-05 CEMENT CONCRETE PAVEMENT	5-14
5-05.1 Description.....	5-14
5-05.3 Construction Requirements.....	5-15
5-05.4 Measurement.....	5-25
5-05.5 Payment.....	5-25
6-02 CONCRETE STRUCTURES	6-1
6-02.3 Construction Requirements.....	6-1
6-02.4 Measurement	6-3
6-02.5 Payment.....	6-3
7-01 DRAINS	7-1
7-01.2 Materials	7-1
7-01.3 Construction Requirements	7-1
7-01.5 Payment	7-1
7-04 STORM SEWERS	7-2
7-04.2 Materials.....	7-2
7-04.3 Construction Requirements.....	7-2
7-04.4 Measurement	7-4
7-04.5 Payment.....	7-5
7-05 MANHOLES, INLETS, CATCH BASINS AND DRYWELLS	7-6
7-05.2 Materials.....	7-6
7-05.3 Construction Requirements	7-6
7-05.4 Measurement.....	7-15
7-05.5 Payment.....	7-15
7-07 CLEANING EXISTING DRAINAGE STRUCTURES.....	7-18
7-07.3 Construction Requirements	7-18
7-07.5 Payment	7-18
7-08 GENERAL PIPE INSTALLATION REQUIREMENTS.....	7-19
7-08.1 Construction Requirements	7-19
7-08.3 Construction Requirements.....	7-19

7-08.4	Measurement	7-27
7-08.5	Payment.....	7-27
7-09	WATER MAINS	7-29
7-09.1	Description.....	7-29
7-09.2	Materials.....	7-30
7-09.3	Construction Materials	7-30
7-09.4	Measurement	7-37
7-09.5	Payment.....	7-37
7-12	VALVES FOR WATER MAINS.....	7-38
7-12.1	Description	7-38
7-12.2	Materials	7-39
7-12.3	Construction Requirements.....	7-39
7-12.4	Measurement	7-39
7-12.5	Payment.....	7-39
7-14	HYDRANTS	7-40
7-14.2	Materials	7-40
7-14.3	Construction Requirements.....	7-40
7-14.4	Measurement	7-41
7-14.5	Payment	7-42
7-15	SERVICE CONNECTIONS.....	7-42
7-15.1	Description	7-42
7-15.2	Materials	7-42
7-15.3	Construction Requirements.....	7-42
7-15.4	Measurement	7-44
7-15.5	Payment.....	7-44
7-17	SANITARY SEWERS.....	7-45
7-17.2	Materials.....	7-45
7-17.3	Construction Requirements.....	7-45
7-17.4	Measurement	7-48
7-18	SIDE SEWERS	7-49
7-18.1	Description	7-49
7-18.2	Materials	7-49
7-18.3	Construction Requirements	7-49
7-18.4	Measurement.....	7-51
7-18.5	Payment	7-51
7-19	SEWER CLEANOUTS	7-52
7-19.1	Description	7-52
7-19.3	Construction Requirements.....	7-52
8-01	EROSION CONTROL AND WATER POLLUTION CONTROL.....	8-1
8-01.1	Description.....	8-1
8-01.3	Construction Requirements	8-2
8-01.4	Measurement.....	8-5
8-01.5	Payment	8-5
8-02	ROADSIDE RESTORATION.....	8-6
8-02.1	Description	8-6
8-02.2	Materials	8-7
8-02.3	Construction Requirements.....	8-7

8-02.5	Payment	8-17
8-03	IRRIGATION SYSTEMS.....	8-21
8-03.1	Description	8-21
8-03.3	Construction Requirements.....	8-22
8-03.4	Measurement	8-24
8-03.5	Payment.....	8-24
8-04	CURBS, GUTTERS AND SPILLWAYS	8-26
8-04.1	Description	8-26
8-04.2	Materials	8-26
8-04.3	Construction Requirements.....	8-26
8-04.4	Measurement	8-27
8-04.5	Payment	8-28
8-06	CEMENT CONCRETE DRIVEWAY ENTRANCES.....	8-29
8-06.1	Description	8-29
8-06.3	Construction Requirements.....	8-29
8-06.4	Measurement	8-30
8-06.5	Payment	8-30
8-10	GUIDE POSTS.....	8-30
8-10.1	Description.....	8-30
8-10.2	Materials.....	8-31
8-10.3	Construction Requirements	8-31
8-10.4	Measurement.....	8-31
8-10.5	Payment.....	8-32
8-12	CHAIN LINK FENCE AND WIRE FENCE.....	8-32
8-12.3	Construction Requirements	8-32
8-12.4	Measurement.....	8-32
8-12.5	Payment	8-33
8-13	MONUMENT CASES	8-33
8-13.1	Description.....	8-33
8-13.2	Materials	8-33
8-13.3	Construction Requirements	8-34
8-13.4	Measurement.....	8-34
8-13.5	Payment	8-34
8-14	CEMENT CONCRETE SIDEWALKS.....	8-35
8-14.1	Description.....	8-35
8-14.2	Materials	8-35
8-14.3	Construction Requirements	8-35
8-14.4	Measurement.....	8-40
8-14.5	Payment	8-40
8-15	RIPRAP.....	8-41
8-15.5	Payment	8-41
8-20	ILLUMINATION, TRAFFIC SIGNAL SYSTEMS AND ELECTRICAL ..	8-42
8-20.1	Description	8-42
8-20.2	Materials	8-42
8-20.3	Construction Requirements.....	8-42
8-20.3(100)	Communication Cables and Interfaces	8-50
8-20.3(101)	Video, Voice, and Data Transmission and Distribution Systems.....	8-56

8-20.4	Measurement	8-56
8-20.5	Payment	8-57
8-21	PERMANENT SIGNING	8-59
8-21.1	Description	8-59
8-21.2	Materials	8-60
8-21.3	Construction Requirements	8-60
8-21.4	Measurement	8-61
8-21.5	Payment	8-61
8-22	PAVEMENT MARKING.....	8-62
8-22.2	Materials.....	8-62
8-22.3	Construction Requirements.....	8-62
8-22.4	Measurement	8-65
8-22.5	Payment.....	8-66
8-23	TEMPORARY PAVEMENT MARKINGS.....	8-66
8-23.4	Measurement	8-66
8-23.5	Payment.....	8-66
8-101	TRAFFIC ISLANDS.....	8-67
8-101.1	Description	8-67
8-101.2	Materials	8-67
8-101.3	Construction Requirements	8-67
8-101.4	Measurement	8-69
8-101.5	Payment	8-69
8-102	CEMENT CONCRETE INTEGRAL CURB AND SIDEWALK	8-69
8-102.1	Description.....	8-69
8-102.2	Materials.....	8-70
8-102.3	Construction Requirements.....	8-70
8-102.4	Measurement.....	8-70
8-103	SEWER PUMP SYSTEMS AND STARTUP.....	8-70
8-103.1	Description.....	8-70
8-103.2	Materials.....	8-70
8-101.3	Construction Requirements	8-72
8-103.4	Measurement.....	8-73
8-103.5	Payment.....	8-73
8-104	REMOVABLE BOLLARDS.....	8-73
8-104.1	Description.....	8-74
8-104.4	Measurement.....	8-74
8-104.5	Payment.....	8-74
8-105	PRECAST CONCRETE WHEEL STOP	8-74
8-105.1	Description.....	8-74
8-105.2	Materials.....	8-74
8-105.4	Measurement.....	8-74
8-105.5	Payment.....	8-74
9-02	BITUMINOUS MATERIALS	9-1
9-02.100	Asphalt Seal Coating.....	9-3
9-03	AGGREGATES.....	9-3
9-03.8	Aggregates for Hot Mix Asphalt	9-3
9-03.9	Aggregates for Ballast and Crushed Surfacing.....	9-4

9-03.12 Gravel Backfill	9-5
9-03.15 Native Material for Trench Backfill.....	9-6
9-03.21 Recycled Material	9-6
9-04 JOINT AND CRACK SEALING MATERIALS.....	9-7
9-04.5 Flexible Plastic Gaskets.....	9-7
9-05 DRAINAGE STRUCTURES, CULVERTS AND CONDUITS.....	9-7
9-05.0 Acceptance by Manufacturer's Certification	9-7
9-05.1 Drain Pipe	9-7
9-05.2 Underdrain Pipe.....	9-8
9-05.9 Steel Spiral Rib Storm Sewer Pipe.....	9-8
9-05.10 Steel Storm Sewer Pipe	9-8
9-05.11 Aluminum Storm Sewer Pipe	9-8
9-05.12 Polyvinyl Chloride (PVC) Pipe	9-8
9-05.15 Metal Castings	9-9
9-05.17 Aluminum Spiral Rib Storm Sewer Pipe.....	9-10
9-05.19 Corrugated Polyethylene Culvert Pipe, Couplings and Fittings	9-10
9-05.20 Corrugated Polyethylene Storm Sewer Pipe	9-10
9-05.21 Steel Rib Reinforced Polyethylene Culvert Pipe	9-10
9-05.21 Steel Rib Reinforced Polyethylene Storm Sewer Pipe	9-10
9-05.23 High-Density Polyethylene (HDPE) Pipe.....	9-10
9-05.24 Polypropylene Culvert Pipe, Polypropylene Storm Sewer Pipe, and Polypropylene Sanitary Sewer Pipe High-Density Polyethylene (HDPE) Pipe	9-10
9-05.50 Precast Concrete Drainage Structures.....	9-11
9-05.100 Cast Iron Pipe.....	9-12
9-06 STRUCTURAL STEEL AND RELATED MATERIALS.....	9-13
9-06 Bolts.....	9-13
9-06.16 Roadside Sign Structures	9-13
9-09 TIMBER AND LUMBER.....	9-13
9-09.2 Grade Requirements	9-13
9-12 MASONRY UNITS	9-14
9-12.2 Concrete Brick	9-14
9-13 RIP RAP, QUARRY SPALLS, SLOPE PROTECTION AND ROCK WALLS	9-14
9-13.7 Rock for Rock Wall	9-14
9-14 EROSION CONTROL AND ROADSIDE PLANTING.....	9-14
9-14.1 Soil.....	9-14
9-14.3 Fertilizer.....	9-15
9-14.4 Mulch and Amendments	9-15
9-14.6 Plant Materials.....	9-16
9-14.7 Stakes, Guys and Wrapping.....	9-16
9-14.100 Anti-Desiccants.....	9-16
9-15 IRRIGATION SYSTEM	9-16
9-15.1 Pipe, Tubing and Fittings.....	9-16
9-15.7 Control Valves	9-17
9-15.8 Quick Coupling Equipment	9-17
9-23 CONCRETE CURING MATERIALS, ADMIXTURES	9-17

9-23.2	Liquid Membrane-Forming Concrete Curing Compounds.....	9-17
9-23.6	Chemical Admixtures for Concrete.....	9-18
9-29	ILLUMINATION, SIGNAL AND ELECTRICAL.....	9-18
9-29.1	Conduit, Innerduct, and Outerduct.....	9-18
9-29.2	Junction Boxes.....	9-19
9-29.3	Fiber Optic Cable, Electrical Conductors, and Cable	9-20
9-29.9	Ballasts	9-26
9-29.10	Luminaires.....	9-26
9-29.11	Control Equipment	9-29
9-29.12	Electrical Splice Materials.....	9-29
9-29.17	Signal Head Mounting Brackets and Fittings	9-30
9-29.17	Signal Head Mounting Brackets and Fittings	9-30
9-29.19	Pedestrian Push Buttons	9-30
9-29.24	Service Cabinets	9-31
9-30	WATER DISTRIBUTION MATERIALS	9-35
9-30.1	Pipe	9-35
9-30.2	Fittings	9-36
9-30.3	Valves	9-38
9-30.5	Hydrants.....	9-41
9-30.6	Water Service Connections (2 Inches and Smaller).....	9-43
9-34	PAVEMENT MARKING MATERIAL	9-44
9-34.3	Plastic	9-44
9-35	TEMPORARY TRAFFIC CONTROL MATERIALS	9-44
9-35.4	Sequential Arrow Signs	9-44
9-100	CHANNELIZING DEVICES	9-45
9-100.1	Materials	9-45

APPENDIX A - DETAIL DRAWINGS

APPENDIX C - CITY/ STATE/ FEDERAL FUNDING REQUIRED INSERTS

APPENDIX D - QUANTITY ESTIMATES

APPENDIX E - PERMITS

APPENDIX H - TRAFFIC SIGNS

APPENDIX I - SIGNALIZATION FURNISH/INSTALL RESPONSIBILITIES

APPENDIX J - SIGNALIZATION WIRING CHARTS

APPENDIX P - PROPOSAL

APPENDIX W - WAGE RATES INFORMATION

APPENDIX Z - PAYMENT ITEMS

CALL FOR BIDS

Riverside Drive Phase 2B

Engineering Services File No. 2015078

This project consists of the construction of approximately 240 cubic yards of excavation and embankment, 1,530 linear feet of water main (varying sizes), 40,320 s.y. of 2-inch thick HMA, 12,310 s.y. of 3 inch thick HMA, and 4,300 s.y. of 3.5-inch thick HMA, construction of a roundabout with concrete and colored concrete islands and center, storm sewer, storm drainage and treatment areas, landscaping, utility conduit construction, pedestrian hybrid bacon system, installation of a traffic signal system lighting and electrical work, sundry utility adjustments, contaminated soil remediation, and other related miscellaneous items.

The City of Spokane Purchasing Department, Fourth floor, City Hall, 808 West Spokane Falls Boulevard, Spokane WA 99201-3316, will receive sealed bids until 1:00 p.m., March 19, 2018 for the above project located in Spokane, Washington, in accordance with the Contract Documents on file at the Department, Engineering Services. The bids will be publicly opened and read at 1:15 p.m. in the City Council Chambers.

Copies of the Contract Documents are available at www.cityofspokaneplans.com. The Planholders list is also available at this website. Additional project information including the Engineer's estimated cost range for the project, bid results (after bid opening), as well as information about other City projects are available by following the appropriate links at the following website: www.spokaneengineering.org/bid-information.

The City of Spokane, in accordance with Title VI of the Civil Rights Act of 1964, 78 Stat. 252, 42 U.S.C. 2000d to 2000d-4 and Title 49, Code of Federal Regulation, Department of Transportation, subtitle A, Office of the Secretary, Part 21, Nondiscrimination in Federally-Assisted Programs of the Department of Transportation issued pursuant to such Act, hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement, disadvantaged business enterprises as defined at 49 CFR Part 26 will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin, or sex in consideration for an award.

Bids shall be submitted on the forms provided in accordance with the provisions of the Specifications. Irregular bid proposals will be rejected in accordance with the specifications.

Cash, cashier's check, a certified check or surety bond in the sum of five percent (5%) of the Total Project Bid must accompany the copy of the bid filed with the City Clerk. Successful bidder shall execute the Contract within FIVE (5) calendar days after

receiving the Contract. Should the successful bidder fail to enter into such contract and furnish satisfactory performance bond within the time stated herein, the bid proposal deposit shall be forfeited to the City of Spokane.

The City of Spokane will normally award this Contract or reject bids within FORTY FIVE (45) calendar days after the time set for the bid opening. If the lowest responsible Bidder and the City of Spokane agree, this deadline may be extended. If they cannot agree on an extension by the 45-calendar day deadline, the City of Spokane reserves the right to Award the Contract to the next lowest responsible Bidder or reject all Bids.

Note regarding new specifications: The City of Spokane is using WSDOT's 2016 Standard Specifications. Bidder's should allow sufficient time to familiarize themselves with the WSDOT 2016 Standard Specifications prior to bidding the project.

A non-mandatory pre-bid conference will be held at Spokane City hall in the Council Briefing Center (basement) at 808 W. Spokane Falls Blvd. at 9:00 a.m. on Wednesday, March 7, 2018.