

## **APPENDIX D - QUANTITY ESTIMATES**

### **CONTENTS**

- Striping Quantity



## STRIPING QUANTITIES COST ESTIMATE

**PROJECT #** 2015078  
**NAME OF PROJECT** RIVERSIDE DRIVE PHASE 2B  
**Date** February 22, 2018

### STRIPING INSTALLATION

| Linear Feet | Striping Material | Line Width (IN) | Area (SF) |
|-------------|-------------------|-----------------|-----------|
| 4030        | PAINT             | 4               | 1343      |
| 316         | DURABLE           | 4               | 105       |
| 473         | DURABLE           | 8               | 315       |
| 105         | DURABLE           | 12              | 105       |
| 4167        | DURABLE H.A.      | 4               | 1389      |
| 2557        | DURABLE H.A.      | 6               | 1279      |
| 1801        | DURABLE H.A.      | 8               | 1201      |
| 160         | DURABLE H.A.      | 24              | 320       |

### WORD & SYMBOLS INSTALLATION

| QTY. | Material     |
|------|--------------|
| 22   | DURABLE H.A. |

### YELLOW CHANNILIZER

| QTY. |  |
|------|--|
| 1    |  |

### STRIPING REMOVAL

| Linear Feet | Striping Material | Line Width (IN) | Area (SF) |
|-------------|-------------------|-----------------|-----------|
| 170         |                   | 4               | 57        |
| 12          |                   | 6               | 6         |
| 28          |                   | 8               | 19        |

### REMOVE CHANNILIZER

| QTY. |  |
|------|--|
| 29   |  |

